BRUHAT BENGALURU MAHANAGARA PALIKE, YELAHANKA ZONE

Executive Engineeer
Byatarayanapura Division
B.B.M.P., Bangalore - 92

MODIFIED SCHEDULE - B

Name of the Work: Improvements to Roads and Drains at Basavasamithi and Surrounding area in Ward No. 14 (Vidyaranyapura).

Sl. No.	Quantity.	Description	Unit	Rates Quotation by M/s. S S Enterprises Prop: Sri. Nagaraj. M S/O Muniraju. H	
				In Figures	In Words
1	359.69	Earth work Excavation by manual means for drains,canals, waste weir, draft, approach channels, key trenches, foundation of bridges and such simillar works in all kinds of soils , as per drawing and technical specifications, including setting out, shoring, strutting, barricading, caution lights, removal of stumps and other deleterious matter, excavated surface leveled and sides neatly dressed disposing off the excavated stuff or sorting & stacking the selected stuff for reuse in a radius of 50 m and lift upto 1.5 m including cost of labour, tools & other appurtenaces required to complete the work.	Cum	104.00	Rupees One Hundred Four Only
2	39.44	Providing and laying in position Plain Cement Concrete Mix 1:3:6 (M10) for levelling course for all works in foundation. Using 40 mm nominal size graded crushed coarse aggregates and fine aggregates as per relevant IS Codes machine mixed, laid in layers not exceeding 150 mm thickness, well compacted using plate vibrators, including all lead & lifts, cost of all materials of quality, labour, Usage charges of machineries, curing, and all the other appurtenances required to complete the work as per technical specifications.	Cum	5109.00	Rupees Five Thousand One Hundred Nine Only
3	88.40	Providing and laying in position Reinforced cement concrete for all Sub structures of building, Irrigation works, Sub structure works of bridges, Drain works & other parallel works from 0.50m to 3.50 m height. The granite/trap/basalt crushed graded coarse aggregates and fine aggregates as per relevant IS Codes machine mixed with super plasticisers, laid in layers, well compacted using needle vibrators, providing weep holes wherever necesary, including all lead & lifts, cost of all materials of quality, confirming to the requirements of relevant IS codes, labour, Usage charges of machinery, curing and all other appurtenances required to complete the work as per technical specifications. M20 (The cost of steel reinforcement & formwork to be paid separately)	Cum	5893.00	Rupees Five Thousand Eight Hundred Ninety Three Only

Signature of the Contractor

ಕಾರ್ಯಪಾಲಕ ಅಭಿಯಂತರ
Executive Engineer
ಬ್ಯಾಟರಾಯನಪುರ ವಿಭಾಗ
ಬೆಂಗಳೂರು

Scanned with CamScanner

Sl. No.	Quantity.	Description	Unit	Rates Quotation by M/s. S S Enterprises Prop: Sri. Nagaraj. M S/O Muniraju. H	
				In Figures	In Words
4	5.46	Supplying, Fitting and Placing un-coated TMT bar Reinforcement in sub-structure complete as per Drawing and Technical Specifications.		95387.00	Rupees Ninety Five Thousand Three Hundred Eighty Seven Only
5	179.46	Providing and Fixing pre cast Covering Slab made out of CC 1:2:4 with **10cm** thick and Finishing cutting, including form work,curing, including cost of all materials, labour, hire charges of machinery, loading, unloading, lead and lift, transportation etc, copmplete.	Sqm	1072.00	Rupees One Thousand Seventy Two Only
6	359.69	Loading and Unloading of Stone Boulder / Stone aggregates / Sand / Kankar / Moorum. (Tipper 14 m3)	Cum	65.00	Rupees Sixty Five Only
7	460.40	Cost of Haulage Excluding Loading and Unloading Taking output 18 t load and lead 10 km = 180 t.km	T.Km	99.00	Rupees Ninety Nine Only
		EIRL			
E1	7.38	Providing and laying in position plain cement concrete for levelling course for all works in foundation. The granite / trap / basalt crushed graded coarse aggregates and fine aggregates as per relevant IS Codes machine mixed, laid in layers not exceeding 150 mm thickness, well compacted using plate vibrators, including all lead & lifts, cost of all materials of quality, labour, Usage charges of machineries, curing, and all the other appurtenances required to complete the work as per technical specifications. (The cost of steel reinforcement & formwork shall be paid separately **Mix 1:3:6 (M10) Using 20 mm nominal size graded crushed coarse aggregate**	Cum	4906.43	Rupees Four Thousand Nine Hundred Six And Paise Forty Three Only
E2	17.91	Providing and Fixing pre cast Covering Slab 230 mm thick made out of CC 1:2:4 and jelly 20mm Down size with steel reinforcement including form work,curing, including cost of all materials, labour, hire charges of machinery, loading, unloading, lead and lift, transportation etc, complete. As per Engineer incharge	Sqm	3922.31	Rupees Three Thousand Nine Hundred Twenty Two And Paise Thirty One Only

Signture of the Contractor

Executive Engineer
Byatarayanapura Division
BBMP, Bangalore - 92

Scanned with CamScanner

BRUHAT BENGALURU MAHANAGARA PALIKE, YELAHANKA ZONE

Executive Engineeer
Byatarayanapura Division
B.B.M.P., Bangalore - 92

MODIFIED SCHEDULE - B

Name of the Work: Improvements to Roads and Drains at Basavasamithi and Surrounding area in Ward No. 14 (Vidyaranyapura).

Sl. No.	Quantity.	Description	Unit	Rates Quotation by M/s. S S Enterprises Prop: Sri. Nagaraj. M S/O Muniraju. H	
				In Figures	In Words
1	359.69	Earth work Excavation by manual means for drains,canals, waste weir, draft, approach channels, key trenches, foundation of bridges and such simillar works in all kinds of soils , as per drawing and technical specifications, including setting out, shoring, strutting, barricading, caution lights, removal of stumps and other deleterious matter, excavated surface leveled and sides neatly dressed disposing off the excavated stuff or sorting & stacking the selected stuff for reuse in a radius of 50 m and lift upto 1.5 m including cost of labour, tools & other appurtenaces required to complete the work.	Cum	104.00	Rupees One Hundred Four Only
2	39.44	Providing and laying in position Plain Cement Concrete Mix 1:3:6 (M10) for levelling course for all works in foundation. Using 40 mm nominal size graded crushed coarse aggregates and fine aggregates as per relevant IS Codes machine mixed, laid in layers not exceeding 150 mm thickness, well compacted using plate vibrators, including all lead & lifts, cost of all materials of quality, labour, Usage charges of machineries, curing, and all the other appurtenances required to complete the work as per technical specifications.	Cum	5109.00	Rupees Five Thousand One Hundred Nine Only
3	88.40	Providing and laying in position Reinforced cement concrete for all Sub structures of building, Irrigation works, Sub structure works of bridges, Drain works & other parallel works from 0.50m to 3.50 m height. The granite/trap/basalt crushed graded coarse aggregates and fine aggregates as per relevant IS Codes machine mixed with super plasticisers, laid in layers, well compacted using needle vibrators, providing weep holes wherever necesary, including all lead & lifts, cost of all materials of quality, confirming to the requirements of relevant IS codes, labour, Usage charges of machinery, curing and all other appurtenances required to complete the work as per technical specifications. M20 (The cost of steel reinforcement & formwork to be paid separately)	Cum	5893.00	Rupees Five Thousand Eight Hundred Ninety Three Only

Signature of the Contractor

Executive Engineer

Scanned with CamScanner

Sl. No.	Quantity.	Description	Unit	Rates Quotation by M/s. S S Enterprises Prop: Sri. Nagaraj. M S/O Muniraju. H	
				In Figures	In Words
4	5.46	Supplying, Fitting and Placing un-coated TMT bar Reinforcement in sub-structure complete as per Drawing and Technical Specifications.		95387.00	Rupees Ninety Five Thousand Three Hundred Eighty Seven Only
5	179.46	Providing and Fixing pre cast Covering Slab made out of CC 1:2:4 with **10cm** thick and Finishing cutting, including form work,curing, including cost of all materials, labour, hire charges of machinery, loading, unloading, lead and lift, transportation etc, copmplete.	Sqm	1072.00	Rupees One Thousand Seventy Two Only
6	359.69	Loading and Unloading of Stone Boulder / Stone aggregates / Sand / Kankar / Moorum. (Tipper 14 m3)	Cum	65.00	Rupees Sixty Five Only
7	460.40	Cost of Haulage Excluding Loading and Unloading Taking output 18 t load and lead 10 km = 180 t.km	T.Km	99.00	Rupees Ninety Nine Only
		EIRL			
E1	7.38	Providing and laying in position plain cement concrete for levelling course for all works in foundation. The granite / trap / basalt crushed graded coarse aggregates and fine aggregates as per relevant IS Codes machine mixed, laid in layers not exceeding 150 mm thickness, well compacted using plate vibrators, including all lead & lifts, cost of all materials of quality, labour, Usage charges of machineries, curing, and all the other appurtenances required to complete the work as per technical specifications. (The cost of steel reinforcement & formwork shall be paid separately **Mix 1:3:6 (M10) Using 20 mm nominal size graded crushed coarse aggregate**	Cum	4906.43	Rupees Four Thousand Nine Hundred Six And Paise Forty Three Only
E2	17.91	Providing and Fixing pre cast Covering Slab 230 mm thick made out of CC 1:2:4 and jelly 20mm Down size with steel reinforcement including form work,curing, including cost of all materials, labour, hire charges of machinery, loading, unloading, lead and lift, transportation etc, complete. As per Engineer incharge	Sqm	3922.31	Rupees Three Thousand Nine Hundred Twenty Two And Paise Thirty One Only

Signture of the Contractor

Executive Engineer
Byatarayanapura Division
BBMP, Bangalore - 92

Scanned with CamScanner